

## Chapter 3

### Earthwork

The following are changes, additions or deletions to the January 2007, Topic #625-000-007, | Plans Preparation Manual (PPM) - English, for use on Turnpike projects only:

#### 3.5.9 Summary of Earthwork

*Add the following paragraph*

Specify and quantify material necessary to meet the drainage design requirements, such as select material beneath swales, on fill, designed to percolate runoff.