ORLANDO South
ULTIMATE INTERCHANGE

FLORIDA'S TURNPIKE

TOLL 528

2045 MORNING PEAK HOUR
PERCENTAGE CHANGE IN INTERSECTION DELAY

Project Development and Environment (PD&E) Study at Florida's Turnpike (SR 91) and Beachline Expressway (SR 528)
Financial Project ID Number: 438547-1 | Efficient Transportation Decision Making (ETDM) Number: 14294

Map labels

John Young Pkwy

ORANGE COUNTY 423

Presidents Drive ↓42%

Sand Lake Road

↓16%

482

Voltaire Road

Horizon Park Drive ↓2%

FLORIDA'S TURNPIKE

Florida Mall

Orange Blossom Trail

La Quinta Drive

TOLL 528

Landstreet Road ↓22% ↑9%

Auto Market

ORANGE COUNTY 527A

↓69%

↓32%

↓95%

Consulate Dr

↓40%

↑17% Thorpe Road

Bachman Road

↓36%

↓97% Taft Vineland Road

441
92
17

General Drive

Rocket Blvd.

Legend

Legend
Percentage Change in Delay
Compared to No-Build

↓ Decreased
↑ Increased

Chart

Cumulative Intersection Delay (Minutes)

	Value
No-Build	41
Alternative 2 Option 1	10

Table

Intersection	2017	2045 No-Build	2045 Build
	LOS/Delay (secs/veh)		
Sand Lake Rd & Presidents Dr	C/25	E/65	D/38
Sand Lake Rd & OBT	D/43	F/128	F/107
Sand Lake Rd & Horizon Park Dr	B/19	D/50	D/49
OBT & Landstreet Rd	D/47	F/161	F/126
OBT & Turnpike Ramp	C/20	C/27	B/18
OBT & Consulate Dr	C/21	F/102	E/61
OBT & Taft Vineland Rd	D/39	F/86	D/55
Landstreet Rd & SR 528 Off	E/48*	F/280*	N/A
Landstreet Rd & SR 528 On	A*	B/12*	N/A
Consulate Dr & TPK SB Off	D/39	D/42	B/13
Consulate Dr & SR 528 EB Off	D/31*	F/588*	C/30
Taft Vineland Rd & Bachman Rd	D/28*	F/872*	C/28
Thorpe Road & Bachman Rd	B/14*	C/23*	D/27*
Landstreet Rd & Bachman Rd	B/14	C/22	C/24

LOS = Level of service; *Unsignalized (LOS/Delay reported for worst movement)

Alternative 2 - Option 1

Option 2 Results Similar

STATION | 7
Public Information Meeting (5:30 p.m. to 7:30 p.m.) | Tuesday, January 29, 2019
UCF Rosen College of Hospitality Management | 9907 Universal Boulevard | Orlando, FL 32819

FDOT