offing Forum EST D g Requirements (GTR) August 17, 2023









- Introductions
 - Transportation Development Director
 - District Design Engineer
 - GTR Team
 - FTBA & ACEC
- GTR Overview
- Updates for 2023
- Feedback







Andra Diggs II, PE **District Design Engineer**



James E Beverly District Tolls Design Administrator P: 407.264.3646 JamesE.Beverly@dot.state.fl.us



Chelsea Scheid Toll Facilities Eng P: 407.264.3418 Chelsea.Scheid@dot.state.fl.us



Director of Transportation Development





Jeff Kipfinger **Electrical Engineer** P: 407.264.3433 Jeff.Kipfinger@dot.state.fl.us





GTR's Purpose and Need

- Statewide source of toll infrastructure criteria and requirements
- Applies to Turnpike and District new tolling projects and when improvements impact existing toll facility operations or infrastructure
- Applies to managed lanes with a tolling component




Supports all project delivery methods

















- Part 1 Development and Processes
- Part 2 Design Criteria
- Part 3 Plans Production











Notable Updates from 2021 GTR

- PART 1
 - Updated abbreviations and terms
 - Clarified Turnpike Tolls Design review and approval processes
- PART 2

- Clarified PD&E Toll Siting Technical Memorandum (TSTM) requirements
- Added GTR exhibits
- Updated GTR sections and exhibits







Notable Updates from 2021 GTR

- PART 2 (cont.)
 - Updated MSPs (GTR 211.2)
 - Appendix 1 Updated and removed TSP sections
 - Appendix 2 Signing and Pavement Marking at Toll Sites (New)
 - Removed references to Turnpike Design Handbook (TDH)
- PART 3
 - Updated gantry plans submittal requirements
 - Updated pay items



Sites *(New)* FDH)





Part 1 – Development and Processes

- Removed references to Turnpike Design Handbook (TDH)
- Revised term Tolled Lanes (TL)
- Clarified GTR Deviation request process
- Updated Tolls Design website Tolls Design – Florida's Turnpike (floridasturnpike.com)

STATEWIDE TOLLS DESIGN SUPPORT

- Toll Facilities Scope Section 31T (posted 04/14/2023)
- Toll Facilities Staff Hours Form Tab 31T (posted 04/14/2023)
- Toll Facilities Engineer's Estimate Template (posted 04/14/2023)
- GTR Deviation Submittal Letter Template (posted 04/14/2023)
- Toll Siting Technical Memorandum (TSTM) Template (posted 04/14/2023)
- Toll Loop Conduit Salvage Detail (PDF) (CAD) (posted 09/20/2022)

STATEWIDE TOLLS PROJECT MANAGEMENT SUPPORT

- Toll Project Responsibility Matrix (posted 12/13/2022)

The District Production Project Manager must communicate with the Turnpike Production Project Manager who will engage with the Toll Systems Project Manager and the Tolls Design Administrator through each phase of the project. Each project should have a complete matrix that is agreed and accepted by both District and Turnpike Project Managers prior to the Phase II plan submittal.

Toll Facility Code Compliance and Permit Procedures (posted 04/14/2023)



Tolls Design

Home / Business Opportunities / Design / Tolls Design

Project Checklist for Tolls Design Coordination and Support (posted 08/04/2021)


STATEWIDE TOLLS CONSTRUCTION SUPPORT





Part 1 – Development and Processes

- Process for use of Roadside Tolling Cabinet (RTC) sites
 - Proof-of-Concept to be field verified
 - Criteria to be refined based on pilot project's lessons learned and maintenance feedback
 - RTC Sites only available for selected Turnpike pilot projects or at District's request



- (1)categories.
- (2)preliminary TSTM.

Modification for Non-Conventional Projects:

Delete items (1) and (2) above and replace with the following:

RTC Sites and applicable requirements in the GTR must not be used. Use TEB site design criteria for all toll sites.



RTC Sites and associated criteria must not be used without Turnpike Tolls Design and Turnpike Design Engineer approval. See GTR 200 for more information on Toll Site


RTC Site use requests must be submitted in PD&E prior to the draft submittal of the





202 – Toll Siting

(Not to be confused with PD&E Manual Sketch Level process)



202.2 **PD&E Toll Siting**


During alternatives development, as part of the PD&E, a sketch level toll site must be included in each alternative. Sketch level toll sites must apply the appropriate toll site exhibit onto each concept alternative to confirm the basic geometry. The concept plans must have sufficient detail to show that the proposed location can support a viable toll site. They must also illustrate potential infrastructure conflicts that must be mitigated.

Perform the following for sketch level toll site development:

- (1)Assume a separate toll site for each toll gantry during alternatives development.
- (2)Use a GTR TEB site as a sketch for alternatives development.
- (3)Coordinate with Turnpike Tolls Design where a GTR TEB site layout is not feasible.
- (4)Identify and include justification for any required GTR Deviations.

A preliminary TSTM must be prepared for the preferred alternative in accordance with GTR 202.3.









220 – Toll Site Roadway

- Profiles (sags and crests) (0.3% min.)
- Lane, shoulder, and buffer widths
- Shoulder rocking












Exhibit 220.2-1 (New)





222 – Toll Site Signs and Pavement Markings

222.2 Sign TOL-7 "Do Not Stop"


- Sign TOL-7 must be located at least 50 feet from the centerline of the gantry. See (1)Appendix 2 for additional information.
- Sign TOL-7 location must be coordinated to avoid conflict with pull boxes or other (2)obstructions.

222.3 Sign TOL-8 "Authorized Vehicles Only"

- Sign TOL-8 is required at all maintenance pull-off areas. (1)
- Sign TOL-8 must be ground-mounted and located within 12-inches from the end (2)of the concrete barrier adjacent to the maintenance pull-off area access point. See the TEB Site Plans and the RTC Site Plans in GTR 231.

222.4 **Pavement Markings at the Toll Site**

See <u>Appendix 2</u> for pavement marking requirements at the toll site. See the Traffic Engineering Manual (TEM) for pavement marking and EL marker requirements at express lanes.









Appendix 2 (NEW) Signing and Pavement Marking at Toll Sites





223 – Toll Site Construction Phasing Requirements

223.1 **General Requirements**

- Maintain all existing toll operations with no interruption to toll collection during (6) construction.
- Maintain toll operations during construction for express lanes, including dynamic (7) rate setting systems, consistent with the existing tolling plan and operations.



223.3.1 **Temporary Traffic Control Plan (TTCP)**

- (2) construction of the remainder of the toll site.
- (5) analysis and memorandum to be submitted:
 - (a) toll sites.
 - (b) a SunPass only lane.



The installation of the toll gantry foundations must be identified in the construction phasing as early as possible to allow sufficient time for foundation surveys to be included into the toll gantry shop drawings. Additional subphases may be required to accommodate the construction of the toll gantry foundations prior to the

Proposed detours that avoid increased tolling through the detour are preferred. Where such increases cannot be avoided, a memorandum with options to address the impact to customers is required. The following scenarios would require an

The detour sends users to a toll site with a higher toll or through multiple

The detour closes tolled lanes with a cash-only option and sends users to






231 – Toll Site Layout

231.1 General Requirements

(5) Concrete median barrier in accordance with <u>Developmental Standard Plans</u>, Concrete Barrier at Toll Sites must be installed to accommodate median loop pull box installations and median gantry uprights. Use of Developmental Standard Plans requires approval by the FDOT Central Office.

(Reduces the number of plans and details required)










(3 New schemes)






232 – Toll Site Electrical (Reorganized and added Exhibits)














232.9 Toll Site Security

(Clarified site access control for locations where fences and gates are required)
















234.3 – Cable Distance Templates












241.6-1 TEB Foundation


(Standard floor penetration layout)












242.1-2 TEB Electrical Layout (Updated)








250 – Toll Gantries (Updated vendor req's.)

Exhibits separated by vendor

- Exhibit 250.2-1 TransCore Layout
- Exhibit 250.2-2 Conduent Layout
- New Vendor equipment loading added
- Exhibit 250.2-3 Toll Equipment Loads












251 – Toll Gantry Structural

EORs are only responsible for strength and fatigue design compliance for cantilever gantries

(Removed the need for comparative analysis to the original sample calculations)










251 – Toll Gantry Structural

- Minor Update: Exhibits 251.7-1, 251.7-4, 251.7-5, 251.7-6, 251.7-8 thru 251.7-16, 251.7-18 thru 251.7-20
- Replaced: Exhibit 251.7-7






⊕∎©

11/2"











252 – Toll Equipment J-Arms

- Added TEC equipment adjustability
- Lengthened u-bolts

















254 – Equipment Retraction Assembly for Accessible Gantries

3.250"

- Added latch plate u-bolt detail
- Added notes to preparer
- Updated u-bolt details













255 – Gantry Electrical

(Clarification for gantry upright size)












255 – Gantry Electrical

(Added unistrut for TEC neutrality)












255 – Gantry Electrical

(Standardized wire trough layout)














255 – Gantry Electrical

(Provided dedicated power routing from stair to vertical wireway)











270 – Building Permits

Coordinate with the Building Permit Coordinator for the electronic delivery of (8) permitting documentation that is required. E-Submittals files must be under 24mb.

The electronic delivery should conform to the following file naming conventions:

- (a)
- Technical Special ProvisionsFPID TSP.pdf (b)
- (C)
- For each building site, the Building Permit Coordinator has thirty working days from (9)receipt to review and accept the provided building permitting documents. Upon acceptance, the Building Permit Coordinator will forward the documents to BCA and State Fire Marshal for approval. Working day periods do not include weekends, holidays, special events, and work period shut downs prescribed by all applicable contract documents.
- The Building Permit Coordinator's review of the plans prior to letting is for (10)conformance to the documentation requirements. It is the sole responsibility of the AOR/EOR to ensure the permitting documents for BCA and State Fire Marshal approval are complete and correct.

STATEWIDE TOLLS DESIGN SUPPORT

- Toll Facilities Scope Section 31T (posted 04/14/2023)
- Toll Facilities Staff Hours Form Tab 31T (posted 04/14/2023)
- Toll Facilities Engineer's Estimate Template (posted 04/14/2023)
- SGTR Deviation Submittal Letter Template (posted 04/14/2023)
- Toll Siting Technical Memorandum (TSTM) Template (posted 04/14/2023)
- Toll Loop Conduit Salvage Detail (PDF) (CAD) (posted 09/20/2022)

STATEWIDE TOLLS PROJECT MANAGEMENT SUPPORT

- Project Checklist for Tolls Design Coordination and Support (posted 08/04/2021)
- Toll Project Responsibility Matrix (posted 12/13/2022)

The District Production Project Manager must communicate with the Turnpike Production Project Manager who will engage with the Toll Systems Project Manager and the Tolls Design Administrator through each phase of the project. Each project should have a complete matrix that is agreed and accepted by both District and Turnpike Project Managers prior to the Phase II plan submittal.

STATEWIDE TOLLS CONSTRUCTION SUPPORT

Toll Facility Code Compliance and Permit Procedures (posted 04/14/2023)



Tolls Design

Home / Business Opportunities / Design / Tolls Design







Appendix 1 - Updated TSP Sections

- 01 11 00 Summary of Work
- 01 41 26 Building Permits
- 05 50 00 Metal Fabrications
- 09 91 00 Painting
- 23 05 00 General Mechanical Requirements
- 26 05 01 Shop Drawings and Submittals
- 26 05 33 Raceway and Boxes for Electrical Systems
- 26 09 13 Supervisory Control and Data Acquisition System
- 26 32 13 Engine Generator
- 26 36 00 Automatic Transfer Switch
- 27 11 16 Tolling Communications Cabinet
- 28 05 14 Access Control System












Appendix 1 - Removed TSP Sections

- 03 30 00 Cast-in-Place Concrete (incl. in spec. T400)
- 05 06 50 Gantry Hardware (incl. w/ Pay item 735-1-XXX)
- 32 13 14 Fiber Reinforced Concrete Pavement (under review)














Appendix 2 – Signing and Pavement Marking at Toll Sites

(New from TDH; Applies to new and existing toll facilities)












Part 3 – Plans Production

302 – Sub-Components of Toll Facility Plans

(Gantry plans are prepared by each gantry type sub-component)









Part 3 – Plans Production

306 – Pay Items

- Clarified pay items to match engineer's estimate
- 306.1 TEB Sites
 - Pay Items revised: Lump sum for New TEB, Modify TEB and Toll Site Demolition
 - Separate pay item for each gantry (includes gantry electrical)
 - Separate pay items for bollards, sidewalk, etc.

 (b) Toll Gantry, No. (c) Toll Gantry, Acc. (d) Electrical Power Entrance (e) Emergency Gen. (f) Toll Site Pull Bo. (g) Conduit (Open. with the TEB as item (2) below. (h) Performance Tol. (i) Fence Gate (j) Toll Site Perime. (k) Concrete Bump. (l) Guardrail Trans. (m) Guardrail (n) Concrete Sidew. (o) Shoulder Concret. (p) Median Concret. (q) Curb and Gutte (r) Bollards (Permation) (k) Pedestrian/Bicy. (u) Pipe Handrail. (v) Toll Plaza (Moor. (w) Toll Plaza Islam. (x) Concrete Class. (y) Flowable Fill. (z) Delivery of Salw. (aa) Removal of Conc. 		
 (d) Electrical Power Entrance (e) Emergency Ger (f) Toll Site Pull Bo (g) Conduit (Open with the TEB as item (2) below. (h) Performance Tu (i) Fence Gate (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concret (p) Median Concret (q) Curb and Gutte (r) Bollards (Permation) (s) Bullet Rail, Singe (t) Pedestrian/Bicy (u) Pipe Handrail, O (w) Toll Plaza (Mood (w) Toll Plaza Islam (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw (aa) Removal of Concrete 	(b)	Toll Gantry, No
 Entrance (e) Emergency Gen (f) Toll Site Pull Bo (g) Conduit (Open with the TEB as item (2) below. (h) Performance To (i) Fence Gate (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concret (p) Median Concret (q) Curb and Gutte (r) Bollards (Permation) (s) Bullet Rail, Singe (t) Pedestrian/Bicy (u) Pipe Handrail, O (v) Toll Plaza (Mood (w) Toll Plaza Islant (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw 	(c)	Toll Gantry, Acc
 (f) Toll Site Pull Book (g) Conduit (Open with the TEB as item (2) below. (h) Performance Tok (i) Fence Gate (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Transform (m) Guardrail (n) Concrete Sidew (o) Shoulder Concret (p) Median Concret (q) Curb and Gutte (r) Bollards (Permation) (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, Good (w) Toll Plaza (Mood (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw 	(d)	
 (g) Conduit (Open with the TEB as item (2) below. (h) Performance Tu (i) Fence Gate (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concretion (p) Median Concretion (p) Median Concretion (q) Curb and Gutte (r) Bollards (Permation) (s) Bullet Rail, Singe (t) Pedestrian/Bicy (u) Pipe Handrail, Given the second seco	(e)	Emergency Ger
 with the TEB asitem (2) below. (h) Performance Tu (i) Fence Gate (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concrete (q) Curb and Guttee (r) Bollards (Permation) (s) Bullet Rail, Singe (t) Pedestrian/Bicy (u) Pipe Handrail, Generation (w) Toll Plaza (Model) (w) Toll Plaza Island (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw (aa) Removal of Concrete 	(f)	Toll Site Pull Bo
 (i) Fence Gate (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concrete (p) Median Concrete (q) Curb and Gutte (r) Bollards (Permation) (s) Bullet Rail, Singe (t) Pedestrian/Bicy (u) Pipe Handrail, General (N) (v) Toll Plaza (Moorete) (w) Toll Plaza Islant (x) Concrete Class (y) Flowable Fill (z) Delivery of Salve (aa) Removal of Concrete) 	(g)	with the TEB as
 (j) Toll Site Perime (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concrete (q) Curb and Guttee (r) Bollards (Permation) (s) Bullet Rail, Singe (t) Pedestrian/Bicy (u) Pipe Handrail, O (v) Toll Plaza (Moorete) (w) Toll Plaza Islam (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw (aa) Removal of Concrete) 	(h)	Performance Tu
 (k) Concrete Bump (l) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concrete (q) Curb and Gutter (r) Bollards (Permatica) (s) Bullet Rail, Singer (t) Pedestrian/Bicy (u) Pipe Handrail, Grading (v) Toll Plaza (Moord) (w) Toll Plaza Islant (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw (aa) Removal of Concrete 	(i)	Fence Gate
 (I) Guardrail Trans (m) Guardrail (n) Concrete Sidew (o) Shoulder Concre (p) Median Concre (q) Curb and Gutte (r) Bollards (Perma (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, G (v) Toll Plaza (Mood (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salw (aa) Removal of Con 	(j)	Toll Site Perime
 (m) Guardrail (n) Concrete Sidew (o) Shoulder Concrete (p) Median Concrete (q) Curb and Guttee (r) Bollards (Permation) (s) Bullet Rail, Singer (t) Pedestrian/Bicy (u) Pipe Handrail, G (v) Toll Plaza (Moorete) (w) Toll Plaza Islante (x) Concrete Classer (y) Flowable Fill (z) Delivery of Salver (aa) Removal of Concrete) 	(k)	Concrete Bump
 (n) Concrete Sidew (o) Shoulder Concrete (p) Median Concrete (q) Curb and Gutter (r) Bollards (Permation) (s) Bullet Rail, Singer (t) Pedestrian/Bicy (u) Pipe Handrail, Grade (v) Toll Plaza (Moorete) (w) Toll Plaza Islant (x) Concrete Classer (y) Flowable Fill (z) Delivery of Salw (aa) Removal of Construction 	(I)	Guardrail Trans
 (o) Shoulder Conce (p) Median Concre (q) Curb and Gutte (r) Bollards (Perma (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, O (v) Toll Plaza (Mood (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Con 	(m)	Guardrail
 (p) Median Concre (q) Curb and Gutte (r) Bollards (Perma (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, G (v) Toll Plaza (Mood (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Con 	(n)	Concrete Sidew
 (q) Curb and Gutte (r) Bollards (Perma (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, G (v) Toll Plaza (Mod (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Con 	(o)	Shoulder Concr
 (r) Bollards (Perma (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, 0 (v) Toll Plaza (Mood (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Conditional Condi	(p)	Median Concre
 (s) Bullet Rail, Sing (t) Pedestrian/Bicy (u) Pipe Handrail, G (v) Toll Plaza (Mood (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Control 	(q)	Curb and Gutte
 (t) Pedestrian/Bicy (u) Pipe Handrail, ((v) Toll Plaza (Moo (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Con 	(r)	Bollards (Perma
 (u) Pipe Handrail, 0 (v) Toll Plaza (Moo (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Con 	(s)	Bullet Rail, Sing
 (v) Toll Plaza (Mod (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Con 	(t)	Pedestrian/Bicy
 (w) Toll Plaza Islan (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Control 	(u)	Pipe Handrail, (
 (x) Concrete Class (y) Flowable Fill (z) Delivery of Salv (aa) Removal of Control 	(v)	Toll Plaza (Mod
(y) Flowable Fill(z) Delivery of Salv(aa) Removal of Con	(w)	Toll Plaza Islan
(z) Delivery of Salv(aa) Removal of Con	(x)	Concrete Class
(aa) Removal of Cor	(y)	Flowable Fill
	(z)	Delivery of Salv
(bb) Clearing and G		
	(bb)	Clearing and G



Non-accessible Accessible		
wer Service, Toll Site Electrical Metering and Utility Service		
enerator, Permanent – including fuel tank and equipment slab		
Boxes (12"x12", 24"x36", 30"x48")		
en Trench / Directional Bore) excluding conduits associated as defined in item (1)(a) above and the gantry as defined in <i>N</i> .		
Turf (Sodding at each toll site)		
meter Fencing		
nper Guard for Parking Lot		
insition Connection to Rigid Barrier		
ewalk, 6" thick		
ncrete Barrier		
prete Barrier		
tter (Toll Header Curb)		
manent / Removable)		
ingle Rail		
icycle Railing		
I, Guiderail		
odify Existing) - Modifying existing or phased demolition		
and - toll plaza island / lane work		
ss II, Bulkhead		
alvageable Material		
Concrete Pavement, Sidewalks, Slabs, etc.		
Grubbing - total site demolition		





2023 GTR – Industry Comments

- ACEC / FTBA
 - 23 comments provided
 - Implemented 17 of 23 comments
 - Received concurrence from reviewers of non-implemented comments

(Copy of comments and responses available upon request)





Questions? Comments...





James E. Beverly, CPM Tolls Design Administrator JamesE.Beverly@dot.state.fl.us 407.264.3646 Office





